

Materials List

4,000 sq feet white visqueen
15 tubes masonry caulk
15 cans spray paint for coping
Diesel fuel for excavation
3 wheelbarrow wheels
25 7.25-inch masonry blades
Masonry grinding stones for large Milwaukee grinder
25 7.25-inch metal cutting blades
7 7.25-inch skills saw blades for framing
4 rolls 3M duct tape
5 rolls rebar twist ties
5 rolls rebar tie wire
25 pounds 8d duplex nails
25 pounds 16d duplex nails
15 pounds 1.5 inch drywall screws
15 pounds 3 inch drywall screws
1000 20-foot lengths #3 rebar
15 gallons cure and seal (optional)
LOTS of wire for the wire feed welder
½ unit ¾" x 4' x 8' cdx plywood
½ unit 3/8" x 4' x 8' cdx plywood
½ unit 2" x 4" x 8' standard or better
20 1" x 6" x 12'
20 1" x 6" x 10'
20 1" x 4" x 10'
5 bundles of 2" x 1" x 2' stakes
5 bundles of 16" x 1" x 2" stakes
15 2" x 2" x 8'
25 4' steel stakes
25 3' steel stakes
30 chairs (the gizmos that bolt onto the stakes for the purpose of holding 2 x 4
175 yards of road base gravel
150 yards 4000 psi concrete with pea gravel 3/8 inch
2" x 4" x 8' cedar board for screed
2" x 4" x 10' cedar board for screed
2" x 4" x 12' cedar board for screed
10 pieces 2" OD schedule 40 steel pipe 20-foot lengths bent at 7' radius
10 pieces 2" OD schedule 40 steel pipes 20-foot length straight.
Burlap fabric 4,000

Equipment List

Backhoe with Loader

Bobcat

Compactor

Rebar cutter

Power trowel

Pipe bender

Small grinders

Large Milwalkie grinder

Wire feed welder

Concrete trowels, tools, rakes, shovels